WYLE TEST REPORT NO. T56285-01 APPENDIX A.1 NOTICES OF ANOMALY



ORIGINAL NOTICE OF ANOMALY	DATE: 12 May 2009		
NOTICE NO: 1 P.O. NUMBER: 001834	CONTRACT NO: N/A		
CUSTOMER: ILTS/Unisyn	WYLE JOB NO: T56285		
NOTIFICATION MADE TO: <u>Chris Ortiz</u>	NOTIFICATION DATE: 4 May 2009		
NOTIFICATION MADE BY: Wendy Owens	VIA: Phone		
	DATE OF		
CATEGORY: [X] SPECIMEN [] PROCEDURE [] TEST EQUIPMENT	ANOMALY: 4 May 2009		
PART NAME: OpenElect Voting System	PART NO. <u>UNI000001</u>		
	I.D. NO. N/A		
SPECIFICATION: Voting System Performance Guidelines (2005)	PARA. NO. 4.1.2.7		
REQUIREMENTS: Vote scanning and counting equipment for paper-based systems, and al without disruption of normal operation or loss of data, surges of: ± 2 kV AC line to line	Vote scanning and counting equipment for paper-based systems, and all DRE equipment, shall be able to withstand, without disruption of normal operation or loss of data, surges of:		
± 2 kV AC line to earth			
DESCRIPTION OF ANOMALY: The OpenElect Voting System was operated in a simulated voting configuration, the ballot reader was in a shoeshine mode and the audio option was active. A +2 kV lightning pulse at 0°, line to line, was applied to the OpenElect Voting System. As the +2 kV lightning pulse was applied the UPS would switch to battery backup, the ballot reader would stop the shoeshine mode and audio would cut on and off.			
DISPOSITION • COMMENTS • RECOMMENDATIONS: The results were documented and the customer informed of the anomaly. The customer informed Wyle Laboratories that they are sending a UPS with a higher surge rating to resume testing.			
Safety Related	1 □ YES □ NO ☑ N/A		
RESPONSIBILITY TO ANALYZE ANOMALIES AND COMPLY WITH 10 CFR PART 2	: □ CUSTOMER □ WYLE		
CAR Required: ☐ YES ☐ NO CAR No.			
VERIFICATION: PROJECT ENC TEST WITNESS: PROJECT MAIN REPRESENTING: A A COORDINATION OF THE PROJECT MAIN INTERDEPAR COORDINATION OF THE PROJECT MAIN OF THE PROJECT MA	NAGER: Ralet than 5/12/09		

WH-1066, Rev. MAR '09

Page ___1__ of ___1_



ORIGINAL	NOTICE OF ANOMALY	DATE: 12/02/09
NOTICE NO: 2	P.O. NUMBER: 001834	CONTRACT NO: N/A
CUSTOMER:	ILTS/Unisyn	WYLE JOB NO: <u>T56285</u>
NOTIFICATION MADE TO:	Chris Ortiz	NOTIFICATION DATE: 10/28/09
NOTIFICATION MADE BY:	W. Owens	VIA:verbally
	IEN []PROCEDURE []TEST EQUIPMENT	· · · · · · · · · · · · · · · · · · ·
PART NAME:	OpenElect Voting System	PART NO. (see below)
TEST: Temperature	and Power Variation	I.D. NO. <u>(see below)</u>
SPECIFICATION: EAC 20)05 VVSG	PARA. NO. 4.7.1
,		

REQUIREMENTS:

The EUT shall not demonstrate any signs of operational failure or degradation of performance when subjected to a Temperature and Power Variation Test in accordance with section 4.7.1 of Volume II of the VVSG. The purpose of this test is to evaluate system operation under various environmental conditions. The duration of the test is 163 hours, with 48 hours in the environmental test chamber. For the remaining hours, the equipment may be operated at room temperature. This test is similar to the low temperature and high temperature tests of MIL-STD-810-D, Method 502.2 and Method 501.2.

To perform the test, the EUT shall be placed inside an environmental walk-in test chamber and connected to a variable voltage power source. The temperature inside the chamber and the voltage supplied to the hardware shall be varied from 40°F to 100°F and from 105 VAC to 129 VAC. During test performance, the operational functions shall be continuously exercised by the scanning of ballots and the generation of ballots via audio voting. A minimum of 100 ballots per hours shall be scanned.

The following EUT serial numbers shall be tested:

EUT 1	EUT 2	EUT 3*	EUT 4
OVO UNI000004	OVO UNI000002	OVO UNI000003	OVO UNI000001
OVI UNI150006	OVI UNI150004	OVI UNI150005	OVI UNI150003

^{*}configured to generate audio ballots only

WH 1066, Revised. Mar '09 Page <u>1</u> of <u>3</u>



	NOTICE OF ANOMALY	DATE: 12/02/09
NOTICE NO: 2	P.O. NUMBER: 001834	CONTRACT NO: N/A
CUSTOMER:	ILTS/Unisyn	WYLE JOB NO:
NOTIFICATION MADE TO:	Chris Ortiz	NOTIFICATION DATE: (see below)
NOTIFICATION MADE BY:	W. Owens	VIA: verbally

DESCRIPTION OF ANOMALY:

Anomalies occurred during the first three test runs of the Temperature/Power Variation Test. Summaries of each run are provided below.

Run 1

Testing commenced on 8/5/09. During test performance it was discovered that multifeeds and ballot misfeeds had occurred causing the machine totals to be incorrect. The test was restarted with no modifications made to the EUT configurations. However, tighter controls were added to the voting procedures exercised during test performance to control ballot handling.

Run 2

Testing commenced on 9/9/09. During test performance it was discovered that multifeeds had ocuured causing the machine totals to be incorrect. The test was halted due to the failures.

Run 3

Testing commenced on 10/9/09. The test was inadvertently halted due to an unexpected "Special Handling Required" notification received by the tester.

wyle

U laboratories			
	NOTICE OF ANOMALY		DATE: 12/02/09
NOTICE NO: 2	P.O. NUMBER:	34 CONTRACT	T NO:N/A
CUSTOMER:	ILTS/Unisyn	WYLE JOB	NO:T56285
NOTIFICATION MADE TO:	Chris Ortiz	NOTIFICAT	ION DATE: (see below)
NOTIFICATION MADE BY:		VIA:	verbally
	MENTS • RECOMMEND ompleted following the fourth		he test is provided below.
Run 4 Testing commenced on 10/20/09. Prior to test initiation, a specially designed gate was installed on each OVO to prevent multifeeds. A ballot handling error was experienced by the tester on EUT 3. This unit was quarantined due to suspect data. The test was extended to 84 hours to compensate for the reduction in the number of units being tested. The test was completed with no anomalies. Testing did continue on the suspect machine to ensure that tester error had been the cause of the anomaly.			
Safety Related YES	☑ NO Potentia	l 10 CFR Part 21 🔲 YES	S □ NO ⊠ N/A
RESPONSIBILITY TO ANALYZE	E ANOMALIES AND COMPLY WITH	H 10 CFR PART 21: 🗌 CUSTON	MER WYLE
CAR Required: ☐ YES	⊠ NO	CAR No.	
VERIFICATION: TEST WITNESS: REPRESENTING: QUALITY ASSURANCE:	Malay 12/4/29	PROJECT ENGINEER: LAPROJECT MANAGER: LAPROJECT MANA	Devidy Quero 12/2/09



ORIGINAL NOTICE OF ANOMALY	DATE: 12/03/09		
NOTICE NO: 3 P.O. NUMBER: 001834	CONTRACT NO: N/A		
CUSTOMER: ILTS/Unisyn	WYLE JOB NO:		
NOTIFICATION MADE TO: Chris Ortiz	NOTIFICATION DATE: 8/14/09		
NOTIFICATION MADE BY: Wendy Owens	VIA: verbally		
	DATE OF		
CATEGORY: [x]SPECIMEN []PROCEDURE []TEST EQUIPN PART NAME: OVI	NOMALY: 8/14/09 PART NO. UNI150003		
TEST: Acoustic Level and Hearing Aid Compatability			
SPECIFICATION: EAC 2005 VVSG, Volume I			
of Edition Town Live 2003 7 7 B.G., Volume 1	1 ANA. 110.		
The machine shall provide an adjustable volume control from 20 to 100 dB SPL in 10 dB increments with the initial volume level set between 40 to 50 dB, and shall reproduce frequencies over the audible speech range of 315 Hz to 10KHz.			
DESCRIPTION OF ANOMALY: The initial volume level was measured to be greater than the maximum accepted level of 50 dB.			
DISPOSITION • COMMENTS • RECOMMENDATIONS:			
ILTS was notified of the anomaly and performed a source code revision to adjust the initial volume setting. The test was then repeated and the initial volume setting was measure to be 47.2 dBA, which is within the allowable range.			
Safety Related ☐ YES ☒ NO Potential 1	0 CFR Part 21 ☐ YES ☐ NO 図 N/A		
RESPONSIBILITY TO ANALYZE ANOMALIES AND COMPLY WITH 10 CFR P	ART 21: ☐ CUSTOMER ☐ WYLE		
CAR Required: ☐ YES ☒ NO CA	R No.		
VERIFICATION: PROJE	ect Engineer: Wondy Quero 12/3/09		
TEST WITNESS: PROJE	ECT MANAGER: July /alef 12/3/09		
	DEPARTMENTAL DINATION:		
QUALITY ASSURANCE: WWW. 12/4/09			

WH 10,66, Rev. March '09

Page __1_ of __1_

WH 1066, Rev. March '09

Page 1 of 1



U laboratories	·	
ORIGINAL NOTICE OF ANOMALY	DATE: 12/03/09	
NOTICE NO: 5 P.O. NUMBER:001834	CONTRACT NO:N/A	
CUSTOMER: ILTS/Unisyn	WYLE JOB NO: <u>T56285</u>	
NOTIFICATION MADE TO:Chris Ortiz	NOTIFICATION DATE: ongoing	
NOTIFICATION MADE BY: Jack Cobb	VIA: <u>e-mail</u>	
CATEGORY: [x]SPECIMEN []PROCEDURE []TEST EQUIPMENT	DATE OF 11/20/08 through 12/03/09	
PART NAME: OpenElect Voting System	-	
TEST: Source Code Review		
SPECIFICATION: EAC 2005 VVSG, Volume I		
2120 2000 · · · · · · · · · · · · · · · ·		
Software used in voting systems shall meet the essential design a Section 5 of the EAC 2005 VVSG.	and performance characteristics detailed in	
DESCRIPTION OF ANOMALY: Review of the submitted source code modules comprising the OpenElect Voting System revealed deviations from the standard as well as issues with the commenting. These anomalies are documented in detail in the Wyle generated source code review reports on file as raw data.		
DISPOSITION • COMMENTS • RECOMMENDATIONS:		
A technical summary report of all identified standards violations was sent to the Unisyn for resolution. Unisyn then corrected all standards violations and re-submitted the source code for re-review. This process was repeated as many times as necessary, until all identified standards violations were corrected.		
Safety Related ☐ YES ☒ NO Potential 10 CFF	R Part 21 ☐ YES ☐ NO ☒ N/A	
RESPONSIBILITY TO ANALYZE ANOMALIES AND COMPLY WITH 10 CFR PART 21	I: ☐ CUSTOMER ☐ WYLE	
CAR Required: ☐ YES ☐ NO CAR No.	1	
VERIFICATION: PROJECT EN	NGINEER: fretal 12.4.09	
TEST WITNESS: PROJECT M.	ANAGER: 1 Sect March 12-4-09	
· · · · · · · · · · · · · · · · · · ·	<i>V</i>	
REPRESENTING: / INTERDEPAI		
QUALITY ASSURANCE: MUMBEL 12/4/09		

WH 1066, Rev. March '09 Page 1 of 1



ORIGINAL NOTICE OF ANOMALY	DATE: 12/10/09	
NOTICE NO: 6 P.O. NUMBER: 00183	4 CONTRACT NO: N/A	
CUSTOMER: ILTS/Unisyn	WYLE JOB NO:	
NOTIFICATION MADE TO: <u>Chris Ortiz</u>	NOTIFICATION DATE: ongoing	
NOTIFICATION MADE BY: Jack Cobb	VIA: <u>e-mail</u>	
CATEGORY: [x] SPECIMEN [] PROCEDURE [] TEST EDURATION: OpenElect Voting System TEST: Functional Configuration Audit (FCA) SPECIFICATION: EAC 2005 VVSG, Volume II	PART NO I.D. NO. Wyle Mantis Reports	
REQUIREMENTS:		
A Functional Configuration Audit (FCA) of the OVS shall be performed in accordance with Section 6.7 of Volume II of the VVSG. The purpose of the FCA is to verify that the OVS performs as documented in the Unisyn-supplied technical documentation during pre-voting, voting, and post-voting activities and that it meets the requirements of the VVSG. To perform the FCA, the OVS shall be subjected to a series of tests to simulate Election Day activities. These tests are performed to ensure compatibility of voting machine functions at the precinct level using the referenced firmware. DESCRIPTION OF ANOMALY: During performance of the FCA, issues were noted related to system functionality. DISPOSITION • COMMENTS • RECOMMENDATIONS: A report of all identified issues was sent to Unisyn for resolution. Unisyn then corrected all noted issues and the tests were repeated with no anomalies.		
Safety Related ☐ YES ☒ NO Pote	ntial 10 CFR Part 21 ☐ YES ☐ NO ☒ N/A	
RESPONSIBILITY TO ANALYZE ANOMALIES AND COMPLY WITH 10	CFR PART 21: ☐ CUSTOMER ☐ WYLE	
CAR Required: ☐ YES ☑ NO	CAR No.	
VERIFICATION:	PROJECT ENGINEER: Wondy Owens 12/10/09	
TEST WITNESS: F	PROJECT MANAGER: 1 Mach m Packet 12/10/09	
	NTERDEPARTMENTAL COORDINATION:	
QUALITY ASSURANCE: Hushaler 12/15/09		
WH 1066, Rev. March '09	Page <u>1</u> of <u>1</u>	



ORIGINAL NOTICE OF ANOMALY	DATE: 12/15/09	
NOTICE NO: 7 P.O. NUMBER: 00183	CONTRACT NO: N/A	
CUSTOMER: ILTS/Unisyn		
NOTIFICATION MADE TO: Chris Ortiz/Jens Jensen		
NOTIFICATION MADE BY: W. Owens	VIA: <u>e-mail</u>	
CATEGORY: [x]SPECIMEN []PROCEDURE []TEST E	QUIPMENT DATE OF ANOMALY: 11/20/08 through 12/15/09	
PART NAME: OpenElect Voting System		
TEST:TDP Review	I.D. NO	
SPECIFICATION: EAC 2005 VVSG, Volume I		
REQUIREMENTS: The Unisyn Voting Solutions, Inc., OpenElect Voting reviewed for accuracy, completeness, and compliance DESCRIPTION OF ANOMALY:	System (OVS) Technical Data Package (TDP) shall be to the 2005 VVSG.	
requirements. Functional testing also identified operatio of the system. Each anomaly is docum reports on file as raw data. DISPOSITION • COMMENTS • RECOMMENDATE The review results were recorded in a worksheep content of the system.	et that provided the pass/fail compliance to each	
applicable VVSG requirement. Unisyn corrected each nonconformance observation and resubmitted the associated documents for review. This process continued until the TDP complied with all applicable requirements.		
Safety Related ☐ YES ☒ NO Pote	ntial 10 CFR Part 21 ☐ YES ☐ NO ☒ N/A	
RESPONSIBILITY TO ANALYZE ANOMALIES AND COMPLY WITH 10	CFR PART 21: ☐ CUSTOMER ☐ WYLE	
CAR Required: ☐ YES ☑ NO	CAR No.	
VERIFICATION:	PROJECT ENGINEER: WWW. OUR 12/15/0°	
TEST WITNESS:	PROJECT MANAGER: <u>Jack Medel 12/15/0</u> 9	
	NTERDEPARTMENTAL COORDINATION:	
QUALITY ASSURANCE: MONTH 12/16/09		
WH 1066, Rev. March '09	Page <u>1</u> of <u>1</u>	



C labolazories		
ORIGINAL NOTICE OF ANOMALY	DATE: 12/16/09	
NOTICE NO: 8, Rev. A P.O. NUMBER: 001834	CONTRACT NO: N/A	
CUSTOMER: ILTS/Unisyn	WYLE JOB NO: <u>T56285</u>	
NOTIFICATION MADE TO: Chris Ortiz	NOTIFICATION DATE: ongoing	
NOTIFICATION MADE BY: Jack Cobb	_ VIA:	
CATEGORY: [x] SPECIMEN [] PROCEDURE [] TEST EQUIPMENT	DATE OF ANOMALY: 11/20/08 through 12/03/09	
PART NAME: OpenElect Voting System		
TEST: Usability and Accessibility	I.D. NO	
SPECIFICATION: EAC 2005 VVSG, Volumes I and II	PARA. NO. Sections 3 and 6.5	
REQUIREMENTS: Usability and Accessibility Testing of the OVS shall be performed in accordance with Section 3 of Volume I and Section 6.5 of Volume II of the VVSG. The purpose of this testing is to assess the quality of interacting between the voter and the voting system and the effectiveness with which the system provides a comfortable and efficient voting session that provides confidence to the voter that their votes are cast correctly.		
DESCRIPTION OF ANOMALY: During test performace, ten issues were noted to usability of the voting system. Of these issues, two were related to text, seven were considered minor, and one was considered major.		
DISPOSITION • COMMENTS • RECOMMENDATIONS:		
A report of all issues was sent to Unisyn for resolution. Unisyn either corrected the issue or the issue was able to be resolved with no retesting required. When testing was required, no anomalies were noted.		
Note: This is a revision to NOA No. 8 dated 12/15/09. This and typos.	revision corrects grammatical errors	
Safety Related ☐ YES ☒ NO Potential 10 CFF	R Part 21 ☐ YES ☐ NO ☒ N/A	
RESPONSIBILITY TO ANALYZE ANOMALIES AND COMPLY WITH 10 CFR PART 21		
CAR Required: ☐ YES ☐ NO CAR No.		
VERIFICATION: PROJECT EN	IGINEER: LLUMCH QUENO 12/17/09	
TEST WITNESS: PROJECT MA	ANAGER: <u>ful 10 facts 12/17/0</u> 9	
REPRESENTING: INTERDEPAR COORDINATION		
QUALITY ASSURANCE: MUSTON 12/18/09		
WH 1066, Rev. March '09	Page 1 of 1	

A

Α

Page __1_ of __1_