



National Technical Systems  
Environmental & Dynamics Lab  
1601 Dry Creek Dr. #2000  
Longmont, CO 80503

Main: 303-776-7249  
Fax: 303-776-7314

---

**Date:** 6 OCTOBER 2017

**Customer:**

Pro V&V  
700 Boulevard South, Suite 102  
Huntsville, AL 35802

**Purchase Order Number: 2017-013**

---

- A. TEST: Temperature/Power Variation Testing
- B. TEST ITEMS: Dominion Voting System  
See page 2 for Test Item Identification
- C. SPECIFICATIONS:
1. MIL-STD 810D
  2. VVSG 1.0: 2005
  3. ISO 17025:2005

D. RESULTS:

This is to certify that the Dominion Voting System was subjected to the Temperature/Power Variation Test according to the above specifications.

See Page 2 for Summary of Test Results. The Dominion Voting System was returned to Pro V&V for post tests and final evaluation.

Test data, an equipment list, and photographs are attached.

Kellie Barnes,  
Preparer

Bob Polverari,  
Technical Reviewer

John Radman,  
Independent Reviewer



**REVISIONS**

<b>Revision</b>	<b>Reason for Revision</b>	<b>Date</b>
NR	Initial Release	10/06/2017
Rev 1	Corrections to test items and test description	10/06/2017

**TEST ITEM IDENTIFICATION**

Quantity	Sample Description	Serial Number
3	DEM Suite 5.5 Icx Prime	1707101789 VVPAT-KPR0000078345 1707101730 VVPAT-KPR0000078339 1707101887 VVPAT-KPR0000078377

**SUMMARY OF TEST RESULTS**



Upon completion of testing, the test samples were removed from the test fixture and subjected to a visual inspection. No anomalies were noted. The Test Samples were returned to Pro V&V.

**Temperature/Power Variation Testing**

Testing was started on 18 September and completed on 21 September by exposing one (1) of each test sample (see Test Item Identification table above), to Power Variation testing. The samples were subjected to this testing in accordance with MIL-STD 810D and VVSG 1.0: 2005.

The test samples were placed in the chamber and exposed to voltage and temperature variances with a 4 hour dwell per sequence, noting that the power varies every 4 hours for two (2) 24 hour cycles, with the temperature varying every 12 hours for two (2) 24 hour cycles

Started at 117 Vac 50 degrees F, then raised to 129 Vac, lowered to 117 Vac and ambient temperature. Raised chamber to 95 degrees F and repeated power sequence. Reduced temp to 50 degrees F and repeated power sequence.



Power Variation Test Setup



TEST	Power Variation		MJO	PR06888
CUSTOMER	Pro V & V	P/N	see below	S/N see below
TEST ITEM	Dominion Voting systems			
SPECIFICATION	MIL-STD810D and 2005 Voluntary Voting System Guidelines (VVSG)		PARA	Method 514.3, Category 1- Basic Transportation, and Common Carrier.
DATE	TIME	LOG ENTRIES		INITIALS
9/18/17 - 9/21/17		items tested were:  DEM Suite 5.5  S/N's  Icx Prime -1707101789  VVPAT-KPR0000078345  Icx Prime -1707101730  VVPAT-KPR0000078339  Icx Prime -1707101887  VVPAT-KPR0000078377		RP



<p>9/18/17 - 9/21/17</p>	<p>Step 1: Arranged the equipment in the test chamber. Connect as required and provide for power, control, and data service through enclosure wall.</p> <p>Step 2: Set the supply voltage at 117 voltage alternating current.</p> <p>Step 3: Powered the equipment, and perform an operational status check as in Section 4.6.1.5.</p> <p>Step 4: Set the chamber temperature to 50 degrees F, observing precautions against thermal shock and condensation.</p> <p>Step 5: Begin 24 hour cycle.</p> <p>Step 6: At T=4 hrs, lowered the supply voltage to 105 vac.</p> <p>Step 7: At T=8 hrs, raised the supply voltage to 129 vac.</p> <p>Step 8: At T=11:30 hrs, returned the supply voltage to 117 vac and return the chamber temperature to lab ambient, observing precautions against thermal shock and condensation.</p> <p>Step 9: At T=12:00 hrs, raised the chamber temperature to 95 degrees Fahrenheit.</p> <p>Step 10: Repeated Steps 5 through 8, with temperature at 95 degrees Fahrenheit, complete at T=24 hrs.</p> <p>Step 11: Set the chamber temperature at 50 degrees Fahrenheit as in Step 4.</p> <p>Step 12: Repeated the 24 hour cycle as in Steps 5-10, complete at T=48 hrs.</p> <p>Step 13: After completing the second 24 hour cycle, disconnect power from the system and remove it from the chamber if needed.</p> <p>Step 14: Reconnect the system as in Step 2, and continue testing for the remaining period of operating time.</p>	<p>RP</p>
	<p>All systems were operational for 64 hours</p>	
<p>PAGE _____ OF _____</p>	<p>TEST BY Polverari _____ ENGINEER Polverari _____</p>	<p>DATE 9/21/17 _____ GOV'T QAR N/A _____</p>





**END OF REPORT**